Work Order

WO No. **WO/2025/ 0250**

WO Date **29/04/2025**

Contractor Details

S K INTERIOR DECORATORS

No:1/5-B, Kurinji Street,
Contact Number : 98848 81005
M.G.R Nagar, Chennai - 600 083

Contact No : 7200244197 / 9094658786

Email: abdulhafiz197@gmail.com

PAN No: ADGPH2128B

GST No: 33ADGPH2128B1ZC

Invoice To

LIFESTYLE HOUSING AND INFRASTRUCTURE

Gee Gee Universal, 3rd Floor, Door No.2/12, Old no.08,
New No.02, Mc Nichols Road, Chetpet, Chennai-600031.

PAN NO. : AADFL6624N

GST No: 33AADFL6624N1Z4

Site Name : THE PODIUM

Site Address Old No 47/1 47/2 New No.97, G.N.Chetty Road, T.Nagar, Chennai, Tamilnadu-600017.

Site Contact: Mr.Balaji

Subject : Work order for supply and application of DG MS structure painting work in the Podium site for Lifestyle Housing and Infrastructure at T.Nagar, Chennai - 600 017.

Sr.No.	Item Description	Unit	Qty	Rate	Basic Amount
1	**DG Civil work and DG Supply .** **Supply and Apply of metal paint**	SFT	1700.00	85.00	1,44,500.00
2	**FINISHES MISCELLANEOUS WORKS.** **Flat DB - Re Painting Work**	NOS	33.00	1,500.00	49,500.00
3	**MS STAIRCASE PAINTING** **MS PAINTING.**	SFT	2565.00	22.00	56,430.00
				Contract Amt (A)	2,50,430.00
				Total Tax (B)	45,077.40
				Total (A + B)	2,95,507.00

AMOUNT IN WORDS:

RUPEES TWO LAC NINETY-FIVE THOUSAND FIVE HUNDRED SEVEN ONLY.

Scope of Work

For DG MS Structure Painting

1. Surface preparation: Wire brushing/sandblasting to remove rust, oil, scale.
2. One coat of EPIDEC EPOXY - ANTI-CORROSION primer.
3. Application of metal putty/paste for surface smoothness (where required).
4. Light sanding and cleaning.
5. Two coats of VAPOCURE - METAL PAINT - MATT FINISH.
6. Colour code will finish as per the project manager's direction

Materials Required & Coverage

EPIDEC EPOXY - ANTI-CORROSION Primer 5–6 m²/litre/coat

VAPOCURE - METAL PAINT - MATT FINISH 8–10 m²/litre/coat

prathap **Priyank**

Prepared by **Authorized By**

For S K INTERIOR DECORATORS

Authorized Signatory