Work Order

WO No. **WO/2025/ 0100**

WO Date **18/06/2025**

Contractor Details

S K INTERIOR DECORATORS

No:1/5-B, Kurinji Street,
Contact Number : 98848 81005
M.G.R Nagar, Chennai - 600 083

Contact No : 7200244197 / 9094658786

Email: abdulhafiz197@gmail.com

PAN No: ADGPH2128B

GST No: 33ADGPH2128B1ZC

Invoice To

LIFESTYLE HOUSING AND INFRASTRUCTURE

Gee Gee Universal, 3rd Floor, Door No.2/12, Old no.08,
New No.02, Mc Nichols Road, Chetpet, Chennai-600031.

PAN NO. : AADFL6624N

GST No: 33AADFL6624N1Z4

Site Name : BALFORT

Site Address No. 34, 22, Balfour Road, Davidpuram, Kilpauk, Chennai, Tamil Nadu 600010

Site Contact:

Subject : **Work order for supply and application of DG MS structure painting work in the Balfort sitefor Lifestyle Housing and Infrastructure at Kilpauk, Chennai - 600010**

Sr.No.	Item Description	Unit	Qty	Rate	Basic Amount
1	**Painting Work - Others MS PAINTING** **Supply and Apply of metal paint**	SFT	1461.48	95.00	1,38,840.60
				Contract Amt (A)	**1,38,840.60**
				Total Tax (B)	**24,991.30**
				Total (A + B)	**1,63,832.00**

AMOUNT IN WORDS:

RUPEES ONE LAC SIXTY-THREE THOUSAND EIGHT HUNDRED THIRTY-TWO ONLY.

Scope of Work

For DG MS Structure Painting
1. Surface preparation: Wire brushing/sandblasting to remove rust, oil, scale.
2. One coat of EPIDEC EPOXY - ANTI-CORROSION primer.
3. Application of metal putty/paste for surface smoothness (where required).
4. Light sanding and cleaning.
5. Two coats of VAPOCURE - METAL PAINT - MATT FINISH.
6. Colour code will finish as per the project manager's direction

Materials Required & Coverage
EPIDEC EPOXY - ANTI-CORROSION Primer 5–6 m²/litre/coat
VAPOCURE - METAL PAINT - MATT FINISH 8–10 m²/litre/coat

Terms of Payment

Payment will be paid after completion of work

Manoj

Prepared by **Authorized By**

For S K INTERIOR DECORATORS

Authorized Signatory